

TOOLBOX TALKS

Reddan Contractors, 438 Southchurch Road, Southend-on-Sea, SS1 2QA

Tel: 01702 616061

Email: helpdesk@reddan.co.uk

Toolbox Talk Details		
Title	C03 - Material storage	
Reason	Unsafe stacking can lead to collapse and life-changing injuries.	
Outline	This talk covers general points on stacking bricks, kerbstones, timber, pipes and prefabricated panels.	

Stacking

- 1. When handling materials, wear work gloves and safety boots.
- 2. Only stack or store materials in authorised areas; never near doorways, walkways or on fire escape routes.
- 3. Where possible, stack on level, firm surfaces and place on pallets or timbers.
- 4. Never make stacks higher than three times the minimum base width.
- 5. Where possible, stack materials close to the working area to reduce the amount of handling.
- 6. Keep your hands clear of the load if materials are being moved by machinery. Use tag lines if loads need to be controlled.

Bricks, blocks and palleted material

- 1. Ensure the base of the stack is level. Only stack two packs high.
- 2. Ensure the upper pack is loaded squarely onto the lower one.
- 3. If banding is damaged or materials are displaced in the pack, do not stack other materials on top.

Timber

- 1. Racks are the best method of storing smaller timbers.
- 2. Joists, trusses and larger timbers should be placed on bearers.
- 3. Do not stack vertically, leaning against other structures.

Large prefabricated panels

- 1. Stack flat or store secured in designed racks (stillages) and ensure items are secured with banding. Sheets of glass need to be stored individually.
- 2. Do not lean against parts of semi-constructed buildings or temporary structures.
- 3. Do not store upright in an area where panels could be affected by wind.
- 4. Secure if stored at height or in other exposed areas, especially lighter materials (such as insulation).

Pipes and tubes

- 1. Where pipes are small in diameter stack in racks. If large in diameter securely chock at the base.
- 2. Do not stack in pyramids as they can become unstable unless the pipes are banded.
- 3. Large concrete rings must be laid flat so they cannot be moved or rolled by any person, especially children.

Revision Date	Assessed By	Signature
January 2021	Michael Reddan	stfallit